



KAGRA status and Future(O5)

Shinji MIYOKI

**Institute for Cosmic Ray Research
The University of Tokyo**

**June 14th 2023
For NSF, The USA**

History of IFO GW detector development in Japan



KAGRA Collaboration



Collaborators
(~450)

Author List
Members
(~ 170)

Universities,
Institutes
(~100)



KAGRA Highlights

KAGRA highlights that are different from other GWDs such as aLIGO, a VIRGO are


...

- (1) **Underground**
→ Stable Operation owing to low seismic noise.
- (2) **Usage of Cryogenic Mirrors and suspensions**
→ Reduce Thermal Noises
- (3) **Collaboration with Geophysical Laser Strain-meter**



KAGRA Site

- In **Gifu pref.** center of JP.
- **350km** away from **Tokyo** (~2.1 hours from Tokyo to Toyama, ~ 1 hour from Toyama City area)




The border area between **Gifu** and **Toyama**




KAGRA in “Hida” Gneiss


- KAGRA is situated in one of the oldest rock of “Hida Gneiss” in Japan.



KAGRA between Two Faults




Tunnel Position and Alignment



Tunnel Design

- **Slope of 1/300** was selected to drain the water to rivers.
- **Horizontal planes** for each station are prepared for easiness during installing vacuum tanks



Tunnel Position and Alignment


Mozumi Entrance

KAGRA Building




SK

- There are 2-layers structure for each station to utilize the rocks as the SAS suspension stable basis.


su Entrance




Vacuum Ducts in arms and Chambers Set in FY2014




Evolution of KAGRA BNS range until O3GK



Evolution of KAGRA sensitivity to O3GK (2019-20)



LVK GW Observation Status




- iKAGRA - Michelson interferometer at room temperature.
- bKAGRA phase-1 - Michelson interferometer with **cryogenic operation**.
- bKAGRA phase-2 - All elements have been installed.
- O3GK - **Power-Recycling Fabry-Perot** Michelson interferometer (no cryogenic).
- O4 start delays to January, July, December 2022, March 2023, and **24th May 2023**.
- **O4 by LH will be done for 20 months including two months breaks.**
- **O4 by Virgo will join from summer/autumn? 2023.**
- **O4 by KAGRA is separated: from May 24th to June 21st, and 3 months from March/April 2024.**
 - 87K at ETMX mirror, ~250K at ITMX, ITMY and ETMY -> at least ~100K for all mirrors

Expected stories to enhance the Sensitivity from O3GK to O4a

● Expected improvement in sensitivities by upgrades


- **100Hz ~ 400 Hz** : Acoustic Noise reduction by **baffles in MICH area**
MICH/PARCL noise by **control scheme ??** or **PY2L coupling ??**
- **50Hz ~ 100Hz** : Control noise reduction of **Type-B/Bp**
Suspension thermal noise by **cooling after reduction of misc noises.**



Expected stories to enhance the Sensitivity from O3GK to O4a

● Expected improvement in sensitivities by upgrades

- $< \sim 50\text{Hz}$: Control noise reduction of **Type-A**
- $> \sim 400\text{Hz}$: More laser power by **0%SRM** and **high-power** laser if possible
Less optical power loss in **OMC** and **repaired PD**
Less **frequency** noise and Less **intensity** noise



Expected Sensitivity Enhancement Story

- **Expected BNS range sensitivity**

	Mirror temp.	Power at BS	SRM reflectivity	BNS Range	Excess noises & assumed reduction factors
O3GK best	~250 K	30-50 W	70 % tilted	~ 1Mpc	Low Freq. noise Pessimistic laser noise
O4a low	300 K	50 W	70 % tilted → 0%	> 1 Mpc	Low Freq. noise Pessimistic laser noise
O4a high / O4b low	300 K	50 W	0 %	3Mpc	0.3* Low Freq. noise Feasible laser noise
O4b high / O5 low	40 K	30 W	0 %	10Mpc	0.04* Low Freq. noise Feasible laser noise
O4b high / O5 low	40 K	300 W (High Power LAS)	0 %	25Mpc	0.013* Low Freq. noise Feasible laser noise
O5 limited	~33 K	~150 W (High Power LAS)	85 %	~85 Mpc (JGW-T2011662-v13)	no excess Thermal resistance at suspensions
O5 high	22 K	673 W (High Power LAS)	85 %	128Mpc	no excess


- **PRFPMI style will be taken during O4 using an AR-coated (~0% Ref) SRM**

O4a/b Targets


— O3GK best sensitivity

— FPMI


PRFPMI —



KAGRA sensitivity at the start of O4a (2020~23)



KAGRA Optical Configuration (PRFPMI for O4)



What were Done until FY2022

- **Type-A suspension finalization.** -> All health checks were completed. We finally verified that no unwanted contacts inside suspensions and disorders, except for one GAS filter.
 - We found some faults in all suspensions after O3GK, and their repair took huge amount of time (~ 2 years).
- **Temperature control system operation for stabilize GASs in suspensions were verified.**
- **Type-A/B/Bp control noise reduction** -> Succeed to reduce at very lower level except for ETMX in Type-A. We also did for some of Type-B/Bps.
- **Mid-size baffle installation in MICH area and optical dumpers installation in IFI/IMMT/OMC/OMMT tanks** for the scattered/stray light mitigation -> Installation itself was completed. The efficiency should be checked in the sensitivity.
- **Cryostat and Sapphire mirrors cooling** -> Smooth operation, except for one cryocooler restarting. The continuous operation time is over one year at EXC. The only ETMX was cooled around 80K, others are at 250K by just radiation cooling.
- **Mirror height monitoring system** -> was newly made.



What were Done until FY2022

- **Vacuum closing in the MICH area. Vacuum system modification around SRM and PRM (installing GVs to segment the MICH area). Ion pump operation for all vacuum system** -> 10^{-10} [Pa m³ sec] level leak was realized, although two serious leaks at the hermetic pins at BS and EY. In addition, these additional GVs actually saved the time for the repair in the IFI and OMC vacuum tank.
- **OMC was repaired** -> The lower loss was realized. Some scattering light might be necessary to be improved.
- **Laser Intensity Stabilization System improvements** -> RIN $\sim 10^{-8}$ was realized. We need more stability.
- **High power laser preparation** -> HPL can be operated with IMC.
- **Optical simulation of the interferometer including Sapphire birefringence** -> FPMI case could be simulate.
- **CAL system improvements** -> Reliability was recovered for YPcal.


What were Done until FY2022

- PEM instruments such as a Water flow meter around EY area for monitoring the water flow effect on the sensitivity and an Infrasound monitor system for checking the effect of sound on sensitivity
- DGS / AEL upgrade works mainly for O5 are ongoing.
- Interlock system construction has finally start for more reliable system monitoring.
- FPMI / PRFPMI Length and Alignment controls -> The length control of PRFPMI was realized. MICH/PRCL feedforward was also improved. ASC except for PR3 was implemented.

Type-A Seismic Noise Isolator



Top Filter (IP/Fzero) In Type-A




Horizontal Isolation


Inverted Pendulum : $f_{reso} < \sim 0.03 \text{ Hz}$

Vertical Isolation

Filter Zero: Geometrical Anti Spring
($f_{reso} < \sim 0.1\text{Hz}$)



GAS Filters (SF/BF) In Type-A




Horizontal Isolation


Single Wire Suspension : $f_{reso} < \sim 0.5$ Hz

Vertical Isolation


Filter Zero: Geometrical Anti Spring
($f_{reso} < \sim 0.1$ Hz)




Cryo-Payload In Type-A



Sapphire Mirror will be cooled by using heat conduction through its sapphire suspension fibers. (Explained Later)



Type-B Seismic Noise Isolator for BS



Suspension Repairs and Improvements

- **Some of GAS filters at type-A lost their isolation function.**
 - **Progress:** Repair and reconstruction of the tower and cryo-payload was done. Health check were done in air/vacuum.
- **LVDT suffered from too much noises.**
 - **Progress:** Low noise LVDTs have been prepared for all of IX, EX, IY, and EY. The control scheme will be refined with these new LVDTs.
- **Lack of temperature control for GAS in Type-A/B/Bp.**
 - **Progress:** Ribbon heaters were installed. Tests will be done in vacuum.
- **Unstable performance of PR2 and PR3.**
 - **Progress:** PR2 was fixed. PR3 remains to be fixed. The jumping amount has reduced, although still remaining.
- **Traverser control software for PRM/2/3 suspension had bugs resulting in runaway.**
 - **Progress:** The bugs were fixed and a limit switch was installed to avoid runaway.



Health check for Type-A, B, Bp and C

● Background

- Just before O3 commissioning, all suspensions were just mechanically constructed.
- During O3 commissioning, their performance were not systematically investigated at all. Ideally, the following should be checked before using a mirror actuator for IFO LSC/ASC/ALS.
 - ✓ sensor spectrum,
 - ✓ transfer functions,
 - ✓ actuator performance and balance,
 - ✓ low actuator coupling,
 - ✓ enough gap between instruments/sensors,
 - ✓ proper default positions and so on.
- Their resonance damping system also varied in Type-A/B/Bp and C.


● Measures

- We decided to perform all check items as an acceptance check before pumping the vacuum tank that house these suspensions.

→ **Progress:** All suspension health checks have been finished.



Suspension Control Noise Contribution



Result
Control noise was reduced by 2~3 order of magnitude

- We could achieve the target sensitivity in O4 with OBS filter
- Improvements are needed to reach the final target sensitivity



IFO Image

Mid-size baffle installation in the MICH area


- **Stray light mitigation is key issue to clean the sensitivity curve and enhance the data quality by removing non-stational noise**

→ **Progress:**


- (1) Preparation of mid-size baffles in 2019. We have a plan to install them according to the well aligned optical axis of PRFPMI configuration.
- (2) Installation of Baffles for IMC suspensions was completed.
- (3) Installation of Mid-size baffles for PRM/2/3, BS and SRM/2/3 have been completed!



Mid-size baffles



IMC baffles









Optical components Position in IFI



IFO [Image](#)

Baffles for MCI/o/e, PRM/2/3, BS, SRM/2/3




Optical Dumper installation in IFI, OMC

- Stray light mitigation is key issue to clean the sensitivity curve and enhance the data quality by removing non-stational noise

→ Progress:


- (1) All mid-size baffles were installed.
- (2) All necessary optical dumpers were installed for IFI-IMM and OMC-OMM tank.

IFI tank





IFO [Image](#)

IMM tank




Akutsu, Sato, Hirata


Optical Dumpers for OMC-OMM



OMC tank



KAGRA Cryogenic System Outlook



KAGRA Cryogenic System

Cryostat Chamber
Diameter: 2.4m
I/O shields Main


1st cooling stage
(~ 40K)

1st vibration
reduction stage

2nd cooling stage
(~ 4.2K)

2nd vibration
reduction stage

PTC for
Cryo-Payload




PTC for
5-m Radiation
Shield Duct

Cryogenic payload
SOLBLACK coating
low cost, can be
some magnetic

Pulse Tube type
Cryocooler (PTC)
(2nd)
Cryostat Radiation
Shields (1st)

Pulse Tube type
Cryocooler (PTC)
for
Cryostat Radiation
Shields


PTC for
Cryo-Payload




Heat Link Vibration Isolation



*Heatlink
Vibration
Isolation
Towers*



*Wide Angle Baffle
For scattered light
mitigation
(done by AOS)*



Cryo-payload

Cryogenic Payload inside Cryostat




Platform stage

Marionette &
Marionette Recoil
Mass

Intermediate Mass &
Intermediate Recoil

Sapphire Mirror
& Mirror Recoil Mass



BeCu blade springs

Moving mass

*Coil-Magnet
actuators w/
optical sensors*

*Coil-Magnet
actuators
w/ optical sensors*

Total mass - 200 kg

*Height - 2 m * Heat links not shown*

IFO [Image](#)

Cryo-part Improvements

- **Frosting on Mirrors** → Super-low finesse, super-low sensitivity

- **Progress:**

- ✓ We set a new regulation on acceptable vacuum leak level from 10^{-9} Pa m³/sec to 10^{-10} Pa m³/sec.
- ✓ Mass spectrometers were set in each cryostat for monitoring N₂, O₂, H₂O.
- ✓ We established the cooling orders.
- ✓ Heaters were installed on Intermediate mass to enhance the speed of heat up for the emergency cases

- **Present status:**

- ✓ ETMX was cooled around 87K from July 2022. While 250K at ITMX.
 - No serious finesse reduction of 1420 for X-arm FP cavity until now.
- ✓ ITMY and ETMY were cooled around 250K.
 - No serious finesse reduction of 1350 for Y-arm FP cavity until now.

- **Frosting on windows where the oplev light pass through** → Unreliable mirror alignment information, no P/Y damping control for mirrors, No operation of IFO




- **Progress:** Heater were installed around windows on the inner and outer radiation shields.

- **Present status:**

- ✓ No serious frosting at EXC. So no test of heating up was done.
- ✓ We should monitor when the inner/outer radiation shields will be cooler at 10K/40K level by operating cryocoolers for them.



Frosting on Mirrors before O₃GK



- When we cooled the sapphire mirrors, scattered light of green laser can be observed in the camera image.
- This scattered light observed when the mirrors reached below 100 K or 30 K.
- So, it might be due to the residual gas contamination due to the cryogenic pumping effect of mirrors.
- So we gave up cool sapphire mirrors for O₃(GK) in 2019.

More Cryo-part Improvements


- **Short-lifetime cryocoolers for the Radiation shield Ducts** → frosting triggers, time wasting
 - **Progress:** all nasty coolers were replaced with two stage type PT-coolers. The only first stage (~ 40K) is used for cooling the radiation shield duct.
- **Stuck of a moving mass for the rough alignment for mirrors at cryogenic temp** → unenabled us to align test masses
 - **Progress:** New designed moving mass system were installed.



Cooling strategy to minimize frosting **works WELL !**

● Measures and Progress

- We made a sophisticated cooling process to avoid frosting.



- We prepared mass-spectrometer to know the residual components for each cryostat.
- We also learned that too long step 3 in EXC showed O₂/N₂ adsorption and vaporization cycle because the temperature at the “uncooled” refrigerators’ structure inside the cryostat.



IFO [Image](#)

Kimura, CRY

Mirror Height Estimation System

[Yuzurihara, Yokozawa, Yamamoto(ICRR), Toriyama, Shiota (Aogaku)]




● Background

- Mirror Position can be up when the cryo-payload is cooled due to physical stiffness enhancement at the cryogenic temperature.
- We need to keep the position of the mirror at the targeted position for the IFO alignment.
- We need a system to judge the height change of the mirror.

● Measures and Progress

- We prepared the mirror height measuring system using Tcam.
- Tcam : Monitoring mirror position / main, green, pcal beam position / surface of mirror.
- Procedure of automatic system
 - Take Tcam photo.
 - Crop necessary regions and fit them.
 - Tcam photo overlaying mirror circle is uploaded on web server.

X-end



IFO [Image](#)

Output Mode Cleaner Improvement

● Background



- Mirror loss for OMC was larger than designed value. → Less shot noise.
- One of PD for DC readout was broken. → Less shot noise.

● Measures and Progress

- We prepared higher quality mirrors for OMC. 80% → 95% transmittance.
- We fixed the DCPD.
- OFI transmittance performance was checked to be OK.



OMC Setting



OFI Setting





IFO [Image](#)

Aso, Nishino, Akutsu, Tanaka





New Laser Intensity Stabilization

- O4 requirement is 10^{-8} , while 10^{-7} for O3.
- The requirement was satisfied.
- ISS stability should be checked now.





High-Power Laser Preparation

- Maximum power: 60 W (120 W in the future) .
- It was installed in the PSL room KAGRA.
- IMC lock using HPL was realized.



High-Power Laser Preparation

- Optical Path separation between the present fiber laser and HPL
- IMC lock using HPL was realized. More control tuning is necessary.




IFO [Image](#)

Miyakawa, Sako, Kato, Maeda, Uehara, Mio, Moriwaki

IFO preparation status

- PRFPMI with DC-readout configuration is realized.
- A part of the Alignment Sensing Control(ASC) is now being accompanied with PRFPMI+DC-readout to enhance the IFO stability and sensitivity stability.



What are the biggest problems at present


- **We are now suffering from**
 - PR3 ASC was not applied because of time-up before O4a
 - So, we need to adjust PR3 alignment manually every day. It loses ~ 2 hours observation time during O4a.
 - Scattered light in the OMC tank
 - We forgot to mitigate one of stray light in the OMC tank, and it seems to hit on something and it generates the scattered light noise around 100Hz.
 - Type-C suspensions cannot isolate 3~10Hz seismic noise effectively. Because of the seismic noise shock due to even the small scale swarm earthquake near the KAGRA site could down not the FP am control, but the IMC control.

O4b(c) plan

- We resume commissioning, including cooling the mirrors from July 3rd.
 - Switch to high power laser from a fiber laser and more laser power injection.
 - Cryocooler regeneration and all mirror cooling below 100K.
 - Scattered light mitigation in OMC.
 - ASC for PR3 and ITMs.
 - MICH/PRCL control noise reduction.
 - Suspension control noise reduction.
- KAGRA will rejoin O4 again for three months from around spring 2024 with the sensitivity of 10Mpc.
- We would like to enhance the sensitivity more than 10Mpc for maybe the last three months of O4.
- RSE is one of possibilities for O4c.

O5 plan


- **Some suspensions should be improved in their mechanical performance.**
 - PR3, Type-C suspensions, Seismic noise isolation for OMC/IFI area.
- **Control noise reduction for Type-A/B suspensions for the lower frequency range.**
- **RSE introduction**
- **The introduction of Frequency independent/dependent squeezing.**
 - However, it requires the large scale KAKENHI.
- **New sapphire input test mass introduction**
 - To mitigate birefringence -> smooth IFO response as we expect
 - To obtain the same reflectivity -> less contribution of common mode noises such as frequency noise..



Birefringence of Sapphire Substrate


- Birefringence in the sapphire crystals will be a problem in future.
 - However, no serious effects were identified in WFS control.
 - On the other hand, the best sensitivity tends to select off-enter axis on ITMs for the arm FP.
- Search for better crystals was carried out.
- Crystals from a Korean company have better birefringence homogeneity compared to the currently installed TMs and comparable absorption.

- We are in a process of making new ITMs with crystals from this company.
- Hopefully, we can install a new set of ITMs before O5.



O5 plan

- **More stray light mitigation around OMC**
 - To mitigate some noises around 100Hz
- **Full and multi High Power Laser preparation**
 - We have 40W FL and 60W LIGO type laser. 120W should be prepared for the future.
 - Two lasers are always necessary for redundancy at KAGRA.
- **In-vac PD for REFL, etc.**
 - To mitigate acoustic noises around 100Hz according to LV experiences.



Thank you